

## SCHEDULE

Name of Work construction of chabutara at ward no 32 dwvbaloda parshad nidhi

As per SOR :SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD BUILDING-01.01.2015]

S.N.	REF	ITEM DESCRIPTION	UNIT	QTY
--				
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	1.1	In all types of soils.	cum	47.88
2	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	cum	29.98
3	7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:		
	5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	cum	57.45
4	3.13	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work.	cum	2.39
5	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	cum	145.53
6	12.3	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.		
	3.2	50 mm thick	sqm	252.00
7	11.2	Providing and making 12mm thick cement plaster of mix:		
	2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	sqm	142.80
8	14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:		
	15.1	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	sqm	142.80

Asst. Engineer  
Municipal CORPORATION  
Bhilai Charoda

Sub engineer  
Municipal CORPORATION  
Bhilai charoda