

18/16

Office Of Municipal Corporation, Bhilai-Charoda

Name of work : Construction of CC roads at ward 06 dream city main road to school

S.O.R. : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD road -01-01-2015]

S.N.	Code	Description	Unit	Quantity	Rate	Amount
1	3.10	Scarifying Existing Granular Surface to a depth of 50 mm (Scarifying the existing granular road surface to a depth of 50 mm and disposal of scarified material within all lifts and leads up to 1000 meters) as per clause 305.4.3.	cum	1400.00	18.00	25,200.00
2	4.10	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)		80.00	1434.00	1,14,720.00
3	6.6.1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) PCC M-10	cum	80.00	2789.00	2,23,120.00
4	6.6	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) m 30	cum	280.00	4350.00	12,18,000.00
					Total	15,81,040.00
					Say	15,81,000.00

[Handwritten Signature]