

(4) (3)

Office Of Municipal Corporation, Bhilai-Charoda

Name of woi : Construction of CC roads at ward 02 hathkhoj

S.O.R. : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD road -01-01-2015]

S.N.	Code	Description	Unit	Quantity	Rate	Amount
1	3.10	Scarifying Existing Granular Surface to a depth of 50 mm (Scarifying the existing granular road surface to a depth of 50 mm and disposal of scarified material within all lifts and leads up to 1000 meters) as per clause 305.4.3.	cum	1420.00	18.00	25,560.00
2	4.10	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density as per clause 406.)		142.00	1434.00	1,94,628.00
		govt school entrance to high school entrance	cum	#REF!		
3	6.6.1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) PCC M-10	cum	142.00	2789.00	3,96,038.00
4	6.6	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) m 30	cum	284.00	4350.00	12,35,400.00

5	4.13 B	Construction of Shoulders (Construction of shoulders as per clause 408 with selected soil from borrow pits / borrow areas having CBR not less than 12 and shall have L.L. and P.I. not more than 25% and 6% respectively, inclusive of all leads and lifts, including clearing and scrapping of existing surface, providing required cross fall, compacting, watering rolling and royalty charges etc. complete.	31.95	277.00	8850.15
			Total	18,60,476.15	

Say 18,60,000.00

M. S. M. S.