

33

43

Office Of Municipal Corporation Bhilai-Charoda Dist-Durg(C.G.)


NIT

Name of Work- construction of Pavor Block at Ward no-08 muiktidham(एकता नगर) sor- PWD sor Building w.e.f.-1/1/2015

Sn	Item no.	Descreption of item	Q	Unit	Rate
1	1.2	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	2040	sqm	7.2
2	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.			
	3.1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).			
			204.00		
			204.00	cum	2659
3	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.			
	3.1.4	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).	14.08	cum	3552
4	1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	7	cum	371

*[Signature]*  
Sub Engineer

	12.65	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm			
	12.65.2	Pigment Coloured (rubber mould) precast interlock concrete blocks	2040	sqm	632
				Total	
				Say Rs.	

  
 Sub Engineer

Executive Engineer  
 Corporation Bhilai-  
 Charoda