


13

Office Of Municipal Corporation, Bhilai-Charoda

Name of work - WARD NO 24 INDIRA NAGAR PRAGATI NAGAR RCC NALI CONSTRUCTION

S.O.R. : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD Building-01-01-2015]

| No | Code | Description | Unit | Quantity | Rate |
|----|--------|--|------|----------|---------|
| 1 | 1.1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. | CUM | 277.2 | 185.00 |
| 2 | 3.1 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 | CUM | 34.65 | 2659.00 |
| 3 | 2.1 | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. | SQM | 908.60 | 139.00 |
| 4 | 3.2 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1.5:3 | CUM | 169.40 | 4163.00 |
| 5 | 3.12 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Fe 415 | KG | 9811.50 | 54.50 |
| 6 | 1.26.1 | Carriage by mechanical transport upto 5 km lead: earth | CUM | 194.04 | 111.00 |


Sub Engineer

Asst. Engineer

Exec. Engineer