## Office Of Municipal Corporation, Bhilai-Charoda Zone 3 Purv Charoda Ward no 29 CC Road Work ESTIMATE IS BASED ON S.O.R. OF P.W.D. w.e.f. 01/01/2015

S	S.O.R.	Description of item					
No	Ref		Na	lo o orth		Danth	0.5
	1	2	No. 3	length 4	Width 5	Depth 6	Qty 7
1	3.1	<b>Excavation for roadway</b> in soil using including loading in truck for carrying of cut earth to embankment site with all lifts and lead upto1000	5	-	5	0	,
		meters as per relevant clauses of section 300.	1	144.00	4.00	0.10	57.60
			1	144.00	4.00	Total	57.60 57.60
2	4.1 B	Granular Sub-base as per Table:- 400-1				Total	01.00
		By Mix in place method					
		Disintegrated rock i.e moorum having CBR value not less than 20 and P.I. and L.L. not more than 6 and 20 respectively.					
			1	144.00	4.00	0.10	57.60
				111.00	1.00	Total	57.60
3	6.6.1	<b>Providing and laying cement concrete</b> for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads and ODR					
		P.C.C. M-10	1	144.00	4.00	0.10	57.60
						Total	57.60
4	3.1.5	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of form work.					
		P.C.C. M-30	1	144.00	4.00	0.20	115.20
						Total	115.20
		Construction of Shoulders (Construction of shoulders as per clause 408 with selected soil from borrow pits / borrow areas having CBR not less than 12 and shall have L.L. and P.I. not more than 25% and 6% respectively, inclusive of all leads and lifts, including clearing and scrapping of existing surface, providing required cross fall, compacting. watering rolling and royalty charges etc. complete.	2	144.00	0.60	0.30	51.84
			~	144.00	0.00	0.00	01.04