

3

58


Office Of Municipal Corporation Bhilai-Charoda Dist-Durg(C.G.)

NIT

Name of Work- construction of C.C. Road and RCC drain at ward no-13

for- PWD for Road w.e.f.-1/1/2015 and PWD Building w.e.f.-1/1/2015

Sn	Item no.	Description of item	Q	Unit	Rate
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.			
	1.1.1	In all types of soils.	86.4	cum	185
2	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.			

  
Sub Engineer

	3.1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).			
3			14.40	cum	2659
	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.			
	3.2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	36.00	cum	4163
4	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:			

*M/S*

	3.12.1	Thermo-Mechanically treated bars FE 415	1038 kg	54.5
5	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
	2.1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	324 sqm	139
6	1.26	Carriage by mechanical transport upto 5 km lead:		
	1.26.1	Earth	43.2 cum	111
1	3.1	Scarifying Existing Granular Surface to a depth of 50 mm . (Scarifying the existing granular road surface to a depth of 50 mm and disposal of scarified material within all lifts and leads up to 1000 meters ) as per clause 305.4.3.	1380 Sqm	18

*M/S*  
*18/12*

		Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads)			
2	6.6				
	(iv)	P.C.C. M-30	207	cum	4350

*M.P.*  
Sub Engineer

Executive Engineer  
Corporation Bhilai-  
Charoda