

33 11

Office Of Municipal Corporation, Bhilai-Charoda

Name of work - WARD NO 23 PANCHSHEEL NAGAR (SHIKSHIT NAGAR AND ADARSH NAGAR) CHROADA
RCC NALI CONSTRUCTION

S.O.R. : SCHEDULE OF RATES PUBLIC WORKS DEPARTMENT [PWD Building-01-01-2015]

No	Code	Description	Unit	Quantity	Rate
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	CUM	362.16	185.00
2	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8	CUM	45.27	2659.00
3	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	SQM	1187.00	139.00
4	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1.5:3	CUM	221.33	4163.00
5	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Fe 415	KG	4979.70	54.50
6	1.26.1	Carriage by mechanical transport upto 5 km lead: earth	CUM	253.51	111.00


Sub Engineer

Asst. Engineer

Exec. Engineer