

37/15

NAGAR NIGAM BHILAI-CHARODA

NIT

Name Of Work-Construction of Shed at Shiv mandir I -cabin Indira Nagar Samta Colony Ward no-24(New ward-26)

(AS PER PWD BUILDING S.O.R 01.01.2015)

PAGE NO	PARTICULAR	QTY	UNIT	RATE
1.1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.			
	In all types of soils.	14.56	cum	185.00
1.18	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.			
		15.49	cum	371.00
3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.			
3.1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	5.86	cum	2659.00
3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.			
3.2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	11.18	cum	4163.00
3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:			
3.12.1	Thermo-Mechanically treated bars FE 415	877.87	KG	54.50
7.5	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:			
7.5.4	Cement Mortar 1:6 (1 cement : 6 coarse sand)	4.44	CUM	3263.00
2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:			
2.1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	17.04	sqm	139.00
2.1.5	Columns, Pillars, Piers and likes- rectangular or square in shape	14.40	sqm	297.00
2.1.6	Columns, beams & walls- circular or any other geometrical shape other than square and rectangular in all sizes	19.88	sqm	356.00

2.1.7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	31.36	sqm	235.00
12.12	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	25.00	sqm	963
12.7	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.			
12.7.2	Size above 200x300mm	25.40	sqm	646
9.3	Steel work in tubular (round, square or rectangular hollow tubes etc.) structure in built-up sections, trusses and frame work including cutting, hoisting, fixing in position upto a height of 5m above plinth level, consisting of columns trusses, roof and bottom purlins, base plate, holding down bolts, wind ties bracing (if required), bolts, nuts and washers for fastening etc. complete with applying a priming coat of red oxide zinc chromate primer. 9.3.1 Electric resistance or induction butt welded tubes Grade-250	1803.65	kg	88.50
10.12	Supply and fixing of polymer pre-coated galvalume profile sheets (PPGL) of approved size, shape and pitch of corrugation, total coated thickness (TCT) 0.60 mm +/- 5%, epoxy primer on both side of the sheet and colour polyester top coat 18-20 microns and 6-7 microns on bottom. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	120.00	sqm	693.00
9.57	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.9.57.2 SS Grade 304	98.4	kg	525.00
11.2	Providing and making 12mm thick cement plaster of mix:	56.16	sqm	91.50
11.2.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)			
11.3	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:			
11.3.4	In Cement Mortar 1:6 (1 cement : 6 fine sand)	20.00	sqm	107.00
14.15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:			
14.9	Distemping with acrylic washable distemper to give an even shade.	77.16	sqm	38.00