

57 (28)


BOQ - CC ROAD AND RCC NALI WARD 37 LAXMI TAMESHWAR RAJENDRA RAJU YADAV HOUSE

CG PWD SOR ROAD 01.01.2015

S.NO	SOR	ITEM	QTY	UNIT	RATE
1	3.1	Excavation in Soil (by Manual Means.) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	254.85	cum	140.00
2	4.1(B)	Granular Sub-base as per Table:- 400-1 Construction of granular sub-base by providing graded Material, , carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface watering, rolling and compacting with vibratory power roller at OMC to achieve the desired density, complete as per clause 401B By Mix in place method Disintegrated rock i.e moorum having CBR value not less than 20 and P.I. and L.L. not more than 6 and 20 respectively. (For Village roads only)	254.85	cum	460.00
3	6.6.1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads) P.C.C. M-10	191.85	cum	2789.00
4	6.6.4	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.( For Village roads) P.C.C. M-30	287.76	cum	4350.00

कार्यपालन अभियंता  
नगर पालिक निगम  
भिलाई चरौदा

सहायक अभियंता  
नगर पालिक निगम  
भिलाई चरौदा

  
उप-अभियंता  
नगर पालिक निगम  
भिलाई चरौदा