

(Signature)

Office Of Municipal Corporation Bhilai-Charoda Dist-Durg(C.G.)

NIT

Name of Work- construction of RCC drain at ward no-09 Shantipara
sor- PWD sor Building w.e.f.-1/1/2015

Sn	Item no.	Description of item	Q	Unit	Rate
1	1.1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.			
	1.1.1	In all types of soils.	295.2	cum	185
2	3.1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.			
	3.1.2	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	49.20	cum	2659
3	3.2	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.			
	3.2.1	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).			
			123.00	cum	4163
4	3.12	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:			
	3.12.1	Thermo-Mechanically treated bars FE 415			
			3750	kg	54.5

5	2.1	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:			
	2.1.1	Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.			
			1107	sqm	139
6	1.26	Carriage by mechanical transport upto 5 km lead:			
	1.26.1	Earth	206.64	cum	111

Executive Engineer
Municipal Corporation
Bhilai- Charoda